

IFB 15-73

SCOPE OF WORK

Work shall be done on weekdays between the hours of 7:00am and 4:00pm and/or weeknights between 7:00pm and 5:00am for the entire length of the project. The CONTRACTOR shall limit the work to the extent that the CONTRACTOR can return the work area to a safe and passable condition for pedestrian and vehicular traffic at the end of each working period.

The CONTRACTOR shall work weekdays or nights to complete any project that is required within the Contract. **No additional compensation will be made if the CONTRACTOR is directed by the ENGINEER to work nights to complete any job within this Contract.** Also see Special Condition #15 **ROAD CONDITIONS** and Special Condition #17 **SWEEPING**

Fletcher St-Willie St to Dane St

- Cold Plane 1-1/2"
- Remove & reset existing curb
- Construct new concrete sidewalks and wheelchair ramps
- Raise/rebuild structures
- Pave 1-1/2" hot mix asphalt top course
- Install reflective line striping and crosswalks
- Replace wire loops

Rutland St-Princeton Blvd to Westford St

- Cold Plane 1-1/2"
- Raise/rebuild structures
- Pave 1-1/2" hot mix asphalt top course
- Install reflective line crosswalks

Westford St-Stedman St to School St

- Cold Plane 1-1/2"
- Old roadway and track excavation
- New curb alignment between Pine St and Osgood St
- Remove & reset existing curb
- Old roadway and track excavation
- Construct new concrete sidewalks and wheelchair ramps
- Raise/rebuild structures
- Pave 1-1/2" hot mix asphalt top course
- Install reflective line striping and crosswalks

Princeton Blvd-Windsor St to Wilder St

- Cold Plane 1-1/2"
- Remove & reset existing curb
- Construct new concrete sidewalks and wheelchair ramps

- Raise/rebuild structures
- Pave 1-1/2" hot mix asphalt top course
- Install reflective line striping and crosswalks

Middlesex St-Walker St to Pawtucket St

- Remove & reset existing curb
- Construct new concrete sidewalks and wheelchair ramps

Gorham St-Congress St to Maple St

- Cold Plane 1-1/2"
- Remove & reset existing curb
- Construct new concrete sidewalks and wheelchair ramps
- Raise/rebuild structures
- Pave 1-1/2" hot mix asphalt top course
- Install reflective line striping and crosswalks