

Technical Specification & Scope

Scope:

Rip up, remove and dispose existing flooring

Patch/ prep as needed (per manufacturer specifications to install new floating floor)

Supply and install Arbor Crest Resilient Plank floating floor in rooms

008 , 30x34 1020sq ft

005 , 28x34 952sq ft

And 2 ROTC Offices 680 sq ft each

Total of 3332 sq ft

Install 6in cove base all colors on floor and base (TBD)

Color will be Cotton pat.00520

Duration:

Work hours allowed: Monday – Friday 6:00am – 10:00pm

Start Date: June 6, 2016

Finish Date: June 27, 2016

Note:

All furniture will be moved by City