

# Scope of Services

## Mulligan Park Basketball Court Project

88 Plain Street

### Site #3

No work can occur without prior approval from the Superintendent of Parks and Open Spaces

- Remove fencing as needed and stock pile for reuse
- Saw cut and remove broken asphalt debris. Supply and install 3" of new asphalt
- Clean entire surface with compressed air
- Jackhammer and remove two existing basketball standards and footings and dispose
- Install two new basketball standards with 5 – 9/16" gooseneck pole and 6' – 0" overhang. Backboard shall be 42" x 72" rectangular steel with double rim goal
- New footings will be 36" wide x 60" deep poured in place concrete
- City of Lowell will provide the basketball hoops
- Rout and fill all structural cracks with acrylic court patch binder
- Supply and install 24" wide Petro Tact membrane over filled cracks
- Shim low spots with hot asphalt to eliminate all bird baths and overlay entire surface with 2" of hot asphalt
- Reinstall existing fence
- Total area to receive two coats of acrylic resurfacer
- Total area to receive three coats of dark green plexi pave material (manufactured by California Product Corp. or equal).
- Texture coat to contain the proper amount of sand to provide a tough wearing base. Top coat to contain the proper amount of pigment to provide a long lasting and attractive surface
- Supply/install one set of white textured basketball court lines
- Davis Bacon regulations will apply
- Federal/state wage rates/certified payrolls
- General contractor must be a current member of the American Sports Builders Association
- Site visits by appointment only

### ➤ Contact Information

Thomas R. Bellegarde  
Commissioner of Parks and Recreation  
1375 Gorham Street  
Lowell, MA 01852  
Tel: 978-970-4171